ROOT DRAIN, LINCOLN PARK BRANCH OF #1696 SECTION 18 T8N R6E, MT. MORRIS, GENESEE COUNTY

PRELIMINARY REPORT

PREPARED FOR:

GENESEE COUNTY DRAIN COMMISSIONER

4608 BEECHER RD.

FLINT, MI 48532

PREPARED BY:

HANUMAN MARUR, P.E.,

TRANS ENVIRONMENTAL ENGINEERS, INC.

5466 N. GENESEE RD. SUITE L

FLINT, MI 48506

Revised on 12/5/2013



TABLE OF CONTENTS

RIDGE DARIN, LINCOLN PARK BRANCH OF #1646

ı.	SURVEYS OF EXISTING DRAINAGE SYSTEM	4
II.	ANALYSIS OF ADEQUACY OF EXISTING DRAINAGE SYSTEM	6
III.	PROPOSED IMPROVEMENTS	8
IV.	DESIGNS	10
V.	COST ESTIMATES	12
VI.	APPENDIX	14,15
VII.	PRELIMINARY PLAN-FXHIBITS	15

1

DETAILS OF EXISTING DRAINAGE SYSTEM

I. EXISTING DRAINAGE SYSTEM

Location of Project

The proposed drain is a branch of Root Drain located in the South East corner of section 18 T8N R6E, between Clovis Street and Coldwater Road in Mt. Morris Township, Genesee County, Michigan. See enclosed map for details.

Details & Surveys of Existing Drainage System

Existing drainage system is open shallow swale, runs on the rear side of properties located on the South side of Clovis Road and the rear side properties located on the North side of Coldwater Road. The existing swale has no catch basin, drainage flows on the surface westward to the existing root drain on the East side of Elms Road. The existing root drain runs south to north. The existing swale system along the rear of properties is not functional with no catch basin or no defined drainage course. The details of existing drainage system are shown on the plan see exhibit #1 and exhibit #2. Since there is no well defined drainage course, during heavy rains 10 years and above, the drainage flow will accumulate on the rear of the properties, parcels 8 & 9 on the south side of Clovis Road and cause flooding on the back yard of site 8 & 9. The existing root drain, just on the east side of Elms Road is deep and the drainage flows generally in the proposed District can be drained by gravity with underground drainage system and catch basins. The elevation and location of root drain is capable of providing an outlet for this area to drain into the existing root drain by gravity thru underground system.

We have computed the drainage flows and are shown on map sheet 10a and 10b. The details of drainage flows for 10 years, 25 years and 100 years are shown on the map. There is no adequate and safe space for detention and retention storage. There for, we have not considered detention as a solution to solve the existing flooding problem.

In summary there is approximately about 35 to 40 acres of drainage area generating about 23 CFS for 10 year storm, about 28 CFS for 25 years storm and about 32 CFS for 100 years storm. Our preliminary designs are limited to for 10 years storm as per county guidelines.

II. ANALYSIS OF ADEQUACY OF EXISITING SYSTEM

II. ANALYSIS OF ADEQUACY OF THE SYSTEM

The existing drainage system is surface flow drainage with no proper grading of the course with high spots and low spots. Since there is no designated or graded drainage course, the drainage flow will stagnate and accumulate at the low spots, when it rains heavily. Since the area does not have proper graded slopes to drain into the outlet to the root drain, it is causing a flooding problem in the low areas. Presently the low areas are in the rear of the properties, house number 6511, 6491, 6471 and 6479 Clevis Rd.

There seems to be a field tile system, which we cannot determine the size or location. Its location should be field determined and videoed to determine the functionality of the existing tile system.

III. PROPOSED IMPROVEMENTS

III. PROPOSED IMPROVEMENTS

In order to prevent flooding, which occurs for the lack of adequate functioning storm sewer system. The proposed closed drain will be designed for 10 year storm, run off as shown on Exhibit attached. Storm frequency is chosen per county guidelines, the county guidelines are 10 year frequency up to 300 acres. 25 year frequency from 300 acres to 1280 acres and 100 year frequency for acres above 1280 acres. The drainage area in this improvement is about 35 acres; therefore we have chosen 10 year frequency for the design improvements to prevent flooding.

OPTION # 1

We are proposing to open a shallow ditch from station 17+95 to station 25+65 about 770' and there after a closed pipe system to the intersection of the root drain, to provide optional solution. It requires at least 20' wide easement for the entire length of the drainage area.

As we are proposing a combination of open ditches and closed pipes on an optimal basis to provide a solution to the flooding, the existing drain course, which is about 35' south of the, Clovis Rd property lines and we are proposing new drain at about 80' south of the Clovis Rd property line following the existing drainage course with a ditch of about 770' and then closed pipe 18" to 30" to the existing root drain. See enclosed map for details. (Exhibit #1)

We have chosen this location as there are low spots along this course based on field levels and verifications.

OPTION # 2

We are proposing an open shallow swale from station 13+20 down to 7+00, and then closed pipes to meet existing root drain. There is an existing shallow swale course from high point, station 13+20 to station 25+05. See enclosed Exhibit #2.

We have chosen the location of proposed CB #4, as we checked the field, it is the lowest point and it is about 80 L.F. from the south and north property lines accordingly.

IV. PRELIMINARY DESIGNS

IV. PRELIMINARY DESIGNS

The system is designed on a preliminary basis, based on our field surveys and the records that we collected from the township office, Genesee County Drain Commissioner's office and the Genesee County GIS Department.

The details are attached with the report.

Lincoln Branch of Root Drain # 1696 Drainage Computations By Section

For details see attached Preliminary plan. Exhibit # 2

Option # 2 10 YEAR STORM

			Swale Swale					
Slope	0.10%	0.50%	ng Shallow ng Graded	Slope				
늴	386'	109' 205'	770' Existing Shallow Swale 620' Existing Graded Swale	:-			Jes	<u>;</u>
Prop Drainage System	24" 2 4 "	30" 30"		Prop Drainage System			3.5 2.78 27.59 * Project is Limited to 10 year storm. as per county guide lines	
Cumulative Flow (cfc)	18.4 20.04	21.16		Cumulative Flow (cfc)	20.16	23.22	27.59 27.59 ear storm, as p	d 4
<u>Drainage</u> Flow	18.4	1.12		<u>Drainage</u> Flow	20.16	3.06	2.78 2.78 ited to 10 ve	
Instensity of Rainfall (1(10yr)T=30	3.00	3.00 3.00		Instensity of Rainfall	3.5	3.5 7.	3.5 * Project is Lim	
<u> </u>	0.20	0.20		CoefC	0.20	0.20	0.20	
"A" Cumulative	29.00	34.84 38.84		"A" Com	29.00	32.98	38.84	
<u>Drainage Area (A</u> <u>CALC)</u>	3.98	1.86 4.00	25 YEAR STORM	Drainage Area [A CALC]	29.00	3.98	4.00	
#8	4 m	7	YEAR	CB#	4	es c		
Section #	7 7	w 4	12 1	Section #	V-1	. •	•	

100 YEAR STORM

	<u> </u>	SIONE					
	<u> </u>	4					S
	Prop Drainage	NA CALL					st Project is Limited to 10 year storm, as per county guide lines
	Cumulative (LIOW ICIC	23.78	27.10	28.51	31.53	ar storm, as po
	<u>Drainage</u>	8	23.18	3.32	1.41	3.02	ted to 10 ye
instensity of	Rainfall	0C-1/1A0T T	83. 83.	3.8	3.8	3.8	* Project is Limit
	ريمور	7 1307	0.20	0.20	0.20	0.20	
	"A"		29.00	32.98	34.84	38.84	
	Drainage Area	7157	29.00	3.98	1.86	4.00	
	#80 # 40;1409	# 1000	1 4	2 3	3 2	4 1	

_

Lincoln Branch of Root Drain # 1696 **Drainage Computations**

By Section For details see attached Preliminary plan. Exhibit #1

Option #1

10 YEAR STORM

Slope	0.10%	0.50%	0.50%	0.25%	0.30%	0.30%	0.35%	0.10%		Slope								
틝	400,	299'	296	386	109'	205		'077		<u>:</u>								
Prop Drainage System	18"	18"	24"	24"	24"	30"		Open Ditch	Prop Drainage	System								
Cumulative Flow (cfc)	8.78	12.09	14.71	17.40	20.04	21.16	23.56		Cumulative	Flow (cfc)	10.18	14.01	17.04	20.16	23.22	24.51	27.29	Section "4"
<u>Drainage</u> Flow	8.78	3.31	2.62	2.69	2.64	1.12	2.4		Drainage	Flow	10.18	3.83	3.03	3.12	3.06	1.29	2.78	*Project is Limited to Section "4"
Instensity of Rainfall (1(10vr)T=30	3.00	3.00	3.00	3.00	3.00	3.00	3.00		Instensity of	Rainfall	3.50	3.50	3.50	3.50	3.50	3.50	3.50	*Project is
Coef C	0.20	0.20	0.20	0.20	0.20	0.20	0.20			Coef C	0.20	0.20	0.20	0.20	0.20	0.20	0.20	
"A" Cumulative	14.63	20.15	24.52	29.00	32.98	34.84	38.84			"A" Com	14.63	20.15	24.52	29.00	32.98	34.84	38.84	
<u>Drainage Area (A.</u> <u>CALC)</u>	14.63	5.52	4.37	4.48	3.98	1.86	4	25 YEAR STORM	Drainage Area	(A CALC)	14.63	5.52	4.37	4.48	3.98	1.86	4	
6	7	9	5	4	m	7	1	YFAR		#	7	9	5	4	ო	7	1	
Section #	П	2	m	4	5	9	7	25	il .	Section #	Н	2	ĸ	4	5	9	7	

100 YEAR STORM

	i	Siope							
	:	4							
	Prop Drainage	<u>System</u>							
	Cumulative	FIOW CTC	11.06	15.23	18.53	21.91	25.23	26.64	29.66
	<u>Drainage</u>	FIOW	11.06	4.17	3.30	3.38	3.32	1.41	3.02
Instensity of	Rainfall	(1(10Vr))=5 <u>0</u>	3.80	3.80	3.80	3.80	3.80	3.80	3.80
	9		0.20	0.20	0.20	0.20	0.20	0.20	0.20
		E S	14.63	20.15	24.52	29.00	32.98	34.84	38.84
	<u> Drainage Area</u>	A CAIL	14.63	5.52	4.37	4.48	3.98	1.86	4
	į	녱	7	9	2	4	m	7	Н
		marinon #	1	7	æ	4	2	9	7

* NOTE

25 year storm generates about 16% more flow than 10 year storm.

100 year storm generates about 26% more flow than 10 year storm.

Since the Drainage area is less than 300 acres and it is only about 40 acres, we have designed the Drainage System

for 10 year storm, as per County guide lines.

V. PRELIMINARY COST ESTIMATES

V. PRELIMINARY COST ESTIMATES

Opti	ion	#1
------	-----	----

10 YEAR STORM	
770 L.F open ditch @ \$5/L.F	\$ 3850.00
699 L.F. 18" R \$25/L.F.	\$17225.00
791 L.F. 24" R \$30/L.F.	\$23730.00
205 L.F. 30" R \$35/L.F.	\$ 7175.00
7 EACH 4' DIA CB @ \$1750/EACH	\$12250.00
(INCLUDES 1EACH 10' END SECTION)	
CLEAN UP AND LANDSCAPING LUMP SUM(2465 L.F)	\$ 9860.00
COST OF CONSTRUCTION	\$ 74090.00
CONSTRUCTION CONTINGENCIES	\$ <u>15910.00</u>
ESTIMATED PROJECT COST	\$90,000.00
*SEE ENCLOSED MAP EXHIBIT #1	

Option #2


10 YEAR STORM

620 L.F. Grading/Swale @ \$7.50/L.F.	\$ 4650.00
495 L.F. 26"R \$30/L.F.	\$ 14,850.00
205 L.F. 30" R \$35/L.F	\$ 7175.00
2 EACH 4' DIA CB @ 1750	\$ 3500.00
1 EACH 5' DIA CB @ 2000	\$ 2000.00
1 EACH SPECIAL DRAINAGE STRUCTURE/WITH END SECTION	\$ 4000.00
CLEAN UP/LANDSCAPING (1320L.F.)	\$ 5000.00
COST OF CONSTRUCTION	\$ 41,175.00
CONSTRUCTION CONTINGENCIES (20%)	\$ 10,825.00
ESTIMATED PROJECT COST	\$ 52,000.00
WORD SALES ASSESSMENT AND ASSESSMENT ASSESSMENT AND ASSESSMENT AND ASSESSMENT ASSESSM	

^{*}SEE ENCLOSED MAP EXHIBIT #2

THE ABOVE COST ESTIMATE WAS PREPARED BY H. MARUR P.E., TEE INC.


VI. APPENDIX



Rainfall Intensity-Duration-Frequency Curves for Flint, Michigan (Source: Consoer Townsend Master Drainage Plan, 1973) Figure 3.1

FIGURE 4





VII. PRELIMINARY PLAN AND EXHIBITS